

M/s Diamond Cements (Prop. HeidelbergCement India Limited)

Clinkerisation Unit, Narsingarh

Month: Jan.19

TEST REPORT OF STACK MONITORING

Location	S-1	S-2	S-3
Date of Monitoring	22.01.2019	18.01.2019	21.01.2019
Stack Attached to	Bag House of Coal Mill No.-1	Bag House of Coal Mill No.-2	Bag House of Coal Mill No.-3
Particulate Matter (mg/Nm³) Isokinetic Samples	22	23	13

Location	S-4	S-5	S-6
Date of Monitoring	23.01.2019	18.01.2019	09.01.2019
Stack Attached to	Hybrid Filter of Kiln/Raw Mill No. -1	Hybrid Filter of Kiln/Raw Mill No. -2	Reverse Air Bag House (RABH) of Kiln/Raw Mill No. -3
Particulate Matter (mg/Nm³) Isokinetic Samples	17	25	26

Location	S-7	S-8	S-9	S-10
Date of Monitoring	22.01.2019	10.1.2019	10.01.2019	16.01.2019
Stack Attached to	ESP of Clinker Cooler No.-1	ESP of Clinker Cooler No.-2	ESP of Clinker Cooler No.-3	Bag House of Crusher
Particulate Matter (mg/Nm³) Isokinetic Samples	28	16	25	12

** Plant was under planned shutdown, Hence Stack Monitoring could not be conducted.

M/s Diamond Cements (Prop. HeidelbergCement India Limited)

Grinding Unit, Imlai

Month: Jan.19

TEST REPORT OF STACK MONITORING

Location	S-1	S-2	S-3
Date of Monitoring	21.01.2019	28.01.2019	*
Stack Attached to	Bag House of Cement Mill No.-1	Bag House of Cement Mill No.-2	Bag House of Cement Mill No.-3
Particulate Matter (mg/Nm³) Isokinetic Samples	16	15	*

Location	S-4
Date of Monitoring	23.01.2019
Stack Attached to	Bag House of Packing Plant No.- 3
Particulate Matter (mg/Nm³) Isokinetic Samples	18

M/s Diamond Cements (Prop. HeidelbergCement India Limited)

Lime Stone Mines, Patharia

TEST REPORT OF STACK MONITORING

Month: Jan.19

Location	S-1
Date of Monitoring	28.01.2019
Stack Attached to	Bag House of Crusher
Particulate Matter (mg/Nm³) Isokinetic samples	19